


LEGENDA:

- 1. KLIMA KOMORA / AIR HANDLING UNIT; V=2400 m3/h, Qg=39 kW, Qh=20 kW
- 2. PRIGUŠIVAČ BUKE / SOUND ATTENUATOR; L=1000 mm (with AHU)
- 3. ELEKTRO PARNI OVLAŽIVAČ / ELECTRO VAPOR MOISTURIZER; G=16 kg/h
- 4. REGULATOR KONSTANTNOG PROTOKA / CONSTANT FLOW REGULATOR; VAV-A-S 357x357
- 5. REGULATOR KONSTANTNOG PROTOKA / CONSTANT FLOW REGULATOR; VAV-A-S Ø160
- 6. ELEKTROMOTORNA ZAKLOPKA / CHECK VALVE WITH ELECTRICAL ENGINE DRIVE; DA-315-V SA T< 3 SEC
- 7. REGULATOR KONSTANTNOG PROTOKA / CONSTANT FLOW REGULATOR; VAV-A-V Ø315
- 8. HEPA FILTER KLASA 14, V= 2200 m3/h, dP<250 Pa
- 9. HEPA FILTER KLASA 14, V=500 m3/h, Dp<250 Pa
- 10. ELEKTROMOTORNA ZAKLOPKA / CHECK VALVE WITH ELECTRICAL ENGINE DRIVE; DA-200-S, T<3 sec
- 11. PP Klapna / FIRE-FIGHTING FLAP; STF 450X450
- 12. PRIGUŠIVAČ BUKE / SOUND ATTENUATOR; SLL - 600X500X1000
- 13. VENTILATOR KBR -315 DZ, V=2800 m3/h, H=700 Pa
- 14. SIGURNOSNI KABINET BSC B2, V=1160 m3/h
- 15. RASHLADNI AGREGAT / COOLING GENERATOR; AN-A 0907, Qh=20 kW
- 16. STROPNI DIFUZOR / CEILING DIFFUSER; DT-250/PS7/SF
- 17. ODISISNA REŠETKA / EXHAUST GRILLE; BMQ-400x300/SC
- 18. STROPNI DIFUZOR / CEILING DIFFUSER; DT-125/PS7/SF
- 19. ODISISNA REŠETKA / EXHAUST GRILLE; BMQ-200x150/SC
- 20. VENTILATOR M 15/6" SA ZAŠTITNOM REŠETKOM / WITH PROTECTION GRILLE





»I.D.E.A.« doo Sarajevo

Curak 2 Sarajevo

Tel: +387 33 222 003

Fax: +387 33 554 120

E-mail: idea@ideh.net.ba

PROJEKAT / PROJECT:	BSL 3 laboratorij BSL 3 Laboratory UKC Tuzla
INVESTITOR / CONTRACTING AUTHORITY:	European Community European Commission for Bosnia and Herzegovina
Odgovorni projektant / Designed By:	Pavo Cavar, mech.engineer Damir Cavar, mech.engineer
Tehnička kontrola / Checked By:	Refik Pirić, mech.engineer
SADRŽAJ LISTA / TITLE OF THE DRAWING:	HVAC INSTALLATION - SECTION A-A
Faza / Phase:	HVAC
Šifra projekta/ID number:	57 - 12 / 08 - b
Datum / Date:	March 2009
Mjerilo / Scale:	1 : 50
M - 003	List broj / Drawing No: