



EUROPEAN UNION

Delegation of the European Union to Bosnia and Herzegovina

Sarajevo,

October, 2017

**Corrigendum No. 1 to the Tender Dossier**

**Regulation of the Janja Riverbed in Ugljevik - relaunch**

**Ugljevik municipality/Republika Srpska, Bosnia and Herzegovina**

**Publication reference: EuropeAid/139183/DD/WKS/BA**

**Tender no.: EC/BiH/TEN/17/018**

The Tender Dossier is corrected as follows:

**Volume 3: Technical Specifications**

The ACC pipes are replaced by PVC pipes in the second paragraph of Section: Riverbed Slope Protection of Technical specifications as follows:

Over the length of longitudinal concrete stabilisation sills, at every 2.00 m, the sills will feature drainage holes. The drainage holes will be made of PVC pipes  $\Phi$ 50 mm, 60 cm long.

**Volume 4.3.2: Bill of Quantities**

- **Bill II MAIN WORKS**

The ACC pipes are replaced by PVC pipes in "Item Description" of item no 4 of Bill II (Main Works), B (Concrete Works) as follows:

<b>B.</b>	<b>B. BETONSKI RADOVI</b>	<b>B. CONCRETE WORKS</b>				
<b>Nr.</b>	<b>Opis</b>	<b>Item Description</b>	<b>Unit</b>	<b>Quantity</b>	<b>Unit price</b>	<b>Total</b>
					<b>€</b>	<b>€</b>
4	Nabavka, transport i ugrađivanje PVC cijevi $\phi$ 50 mm, dužine 60 cm u podužne stabilizacione pragove na razmaku od 200 cm za dreniranje zaobalnih voda. Obračun radova po komadu ugrađene cijevi. PVC cijev $\phi$ 50 mm/60 cm	Supply, transportation and installation of PVC pipes $\phi$ 50 mm, 60 cm long, into longitudinal stabilisation sills spaced at 200 cm for the drainage of littoral waters. Calculation of works per piece of installed pipe. PVC pipe $\phi$ 50 mm/60 cm	pcs	1,894.00		

- **Bill III-8 STRUCTURE OF THE UPSTREAM TRANSITIONAL SECTION (Ch.3+737,00)**

The ACC pipes are replaced by PVC pipes in "Item Description" of item no 3 of Bill III-8 (Structure of the upstream transitional section (ch.3+737,00)), B (Concrete Works) as follows:

<b>B.</b>	<b>BETONSKI RADOVI</b>	<b>CONCRETE WORKS</b>				
<b>Nr.</b>	<b>Opis</b>	<b>Item Description</b>	<b>Unit</b>	<b>Quantities</b>	<b>Unit price</b>	<b>Total</b>
					<b>€</b>	<b>€</b>
3	Nabavka, transport i ugrađivanje PVC cijevi $\phi$ 50 mm, dužine 60 cm u podužne stabilizacione pragove na razmaku od 200 cm za dreniranje zaobalnih voda. Obračun radova po komadu ugrađene cijevi. PVC cijev f 50 mm/60 cm	Supply, transportation and installation of PVC pipes $\phi$ 50 mm, 60 cm long, into longitudinal stabilisation sills spaced at 200 cm for the drainage of littoral waters. Calculation of works per piece of installed pipe. PVC pipe f 50 mm/60 cm	<b>pcs</b>	<b>8.00</b>		

Please be informed that the corrected Bill of Quantities is attached to this Corrigendum no. 1 as an Annex 1 and the Tenderers are requested to use this corrected Bill of Quantities for preparation of their offer.

All other terms and conditions of the Tender Dossier remain unchanged. The above corrections to the Tender Dossier are integral part of the Tender Dossier.